

舗装工 数量計算書

市道高川原西線

測点	延長	As 取壊し t=4cm			不陸整正 W ≥ 1.8m			表層工 t=4cm		
		断面	平均	数量	断面	平均	数量	断面	平均	数量
No.7		3.50			3.50			3.50		
No.8	20.0	3.50	3.50	70.00	3.50	3.50	70.00	3.50	3.50	70.00
No.9	20.0	3.70	3.60	72.00	3.70	3.60	72.00	3.70	3.60	72.00
No.10	20.0	3.50	3.60	72.00	3.50	3.60	72.00	3.50	3.60	72.00
No.11	20.0	3.10	3.30	66.00	3.10	3.30	66.00	3.10	3.30	66.00
No.11+14.5	14.5	3.40	3.25	47.13	3.40	3.25	47.13	3.40	3.25	47.13
小計	94.5			327.13			327.13			327.13
③		a=3.40	4.28	2.17	a=3.40	4.28	2.17	a=3.40	4.28	2.17
		b=3.85			b=3.85			b=3.85		
		c=1.30			c=1.30			c=1.30		
④		a=3.85	11.88	18.79	a=3.85	11.88	18.79	a=3.85	11.88	18.79
		b=9.90			b=9.90			b=9.90		
		c=10.00			c=10.00			c=10.00		
小計				20.96			20.96			20.96
合計				348.09			348.09			348.09

舗装工 数量計算書

市道農協前長岡線

測点	延長	As 取壊し t=4cm			不陸整正 W ≥ 1.8m			表層工 t=4cm		
		断面	平均	数量	断面	平均	数量	断面	平均	数量
No.0		5.50			5.50			5.50		
No.1	20.0	3.85	4.68	93.50	3.85	4.68	93.50	3.85	4.68	93.50
No.2	20.0	3.15	3.50	70.00	3.15	3.50	70.00	3.15	3.50	70.00
No.3	20.0	3.30	3.23	64.50	3.30	3.23	64.50	3.30	3.23	64.50
No.4	20.0	2.90	3.10	62.00	2.90	3.10	62.00	2.90	3.10	62.00
No.5	20.0	3.00	2.95	59.00	3.00	2.95	59.00	3.00	2.95	59.00
No.5+10.4	10.4	3.00	3.00	31.20	3.00	3.00	31.20	3.00	3.00	31.20
No.5+13.4	3.0	4.80	3.90	11.70	4.80	3.90	11.70	4.80	3.90	11.70
No.6	6.6	4.75	4.78	31.52	4.75	4.78	31.52	4.75	4.78	31.52
No.7	20.0	4.53	4.64	92.80	4.53	4.64	92.80	4.53	4.64	92.80
小計	140.0			516.22			516.22			516.22
合計				516.00			516.00			516.00